

15-185-21415-0000

1 121028 4-13

API NUMBER 15- Docket #D-20,384

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NE, SEC. 11, T 22 S, R 14 W/R

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name Williams Well # 4

Operator: Woodman-Iannitti Oil Company

County Stafford

Name: P.O. Box 308

Well Total Depth 3945 128.21 feet

Address: Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 9 a.m. Day: 13 Month: 4 Year: 1995

Plugging proposal received from Dick Iannitti

(company name) Woodman-Iannitti Oil Co. (phone) 316-792-1922

Work: 4 1/2" at 3870' w/100 sx cement, Open hole 3870-3945', EOC 3000', Bad casing from 730-
1st plug run tubing to 3300' and fill well with cement. 2900'

Plugging Proposal Received by Duane Rankin

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 a.m. Day: 13 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3300' and pumped 60 sx cement,

2nd plug laid down tubing to 2630' and pumped 60 sx cement,

3rd plug laid down tubing to 1624' and pumped 50 sx cement, 4th plug laid down tubing to
760' and pumped 155 sx cement. Cement did not circulate. Had good circulation from the

4 1/2" and 4 1/2" X 8 5/8" annulus throughout. Ran line on 4/17/95 and found top of cement at
270'. Filled with readi-mix from 270-0' on 4/25/95. Used 4 yards of readi-mix by Concrete Ser.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 5-5-95

Signed

(TECHNICIAN)

INV. NO. 42773

FORM CP-2/3
Rev. 01-84