

1 060778

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 1949

NW SW SE, SEC. 12, T 22 S, R 13 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Teichmann Well # 4

Operator: Raymond Oil Company, Inc.
Name & Address P. O. Box 48788
Wichita, KS 67201

County Stafford 119.67
Well Total Depth 3682 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 pm Day: 22 Month: January Year: 19 86

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3675' Open Hole

1st plug sand back to 3620' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:50 pm Day: 22 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3620' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1986
1-27-86
CONSERVATION DIVISION

Maximum pressure 500 psi and shut in 100 psi

Remarks: Recovered 2821' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not observe) observe this plugging.

DATE FEB 5 1986

Signed Paul A. Luthin (TECHNICIAN)

INV. NO. 12371