

To: 1 120728 15-185-22107-0001
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,107
NE SE SE, SEC. 12, T. 22 S, R. 13 W/E
990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5057
Operator: Voight Oil & Gas Co., Inc.
Name
Address Rt. 3, Box 33-B
McPherson, KS 67460

Lease Name Teichmann "B" Well # 1
County Stafford 121.06
Well Total Depth 3725 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 730

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 25 Month: 8 Year: 19 92

Plugging proposal received from Richard Voight
(company name) Voight Oil & Gas Co., Inc. (phone) 913-227-3241

were: 5 1/2" at 3723' w/200 sx cement, PRTD 3664', Perfs at 3398-3640'
1st plug sand back to 3350' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 25 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3350' and dumped 5 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 8 sx gel, 50 sx cement, 7 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Pumping pressure 0-800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1874' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED
I (could not) observe this plugging.
DATE 9-14-92
INV. NO. 36140

9-2-92
RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1992
Signed Duane Rankin
(TECHNICIAN)
CONSERVATION DIVISION
WICHITA, KANSAS
FORM CP-2/3
Rev. 01-84