

To: 1 120670  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-8-92  
API NUMBER 15- 185-22,599-0000 48

E/2 SE NE, SEC. 12, T 22 S, R 13 W/E  
3300 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4958  
Operator: Hess Oil Company  
Name & Address: P.O. Box 1009  
McPherson, KS 67460

Lease Name Teichman A Well # 2  
County Stafford 119.76  
Well Total Depth 3685 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 8 Month: 1 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 3678' w/150 sx cement, Perfs at 3481-3678' (3 sets)

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 8 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3360' and dumped 5 sx cement on sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

Plate & 5 1/2" collar welded on 8 5/8".

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1783' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED

KANSAS CORPORATION COMMISSION observe this plugging.

DATE JAN 29 1992

JAN 16 1992 Signed \_\_\_\_\_

(TECHNICIAN) [Signature]

INV. NO. 34403

CONSERVATION DIVISION WICHITA, KS