

To: 1 071096
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-11 API NUMBER 15- NA 15-083-10246-0000 292

C NE SW, SEC. 21, T. 22 S, R. 22 W. NEK
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: BEREXCO Inc.
Name & Address P.O. Box 723
Hays, KS 67601

Lease Name Ed Miller Well # A 1
County Hodgeman 144.88
Well Total Depth 4458 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor BEREXCO Inc. License Number 5363
Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 4:30 p.m. Day: 10 Month: 9 Year: 19 92

Plugging proposal received from Ted Crawford
(company name) BEREXCO Inc. (phone) 913-628-6101

were: 5 1/2" at 4443' w/100 sx cement, Perfs at 4230-38'
1st plug set CIBP at 4000' and dump 2 sx cement on top,
2nd plug perforate at 600' and pump 650 lbs. hulls and 240 sx cement down 5 1/2",
3rd plug pump 115 sx cement down backside.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 11 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4000' and dumped 2 sx cement on top,
2nd plug perforated at 600', pumped 650 lbs. hulls and 240 sx cement down 5 1/2".

Maximum pressure 500 psi and shut in on vacuum. Shut down.
9/11/92 pumped 10 sx cement down 5 1/2", Maximum pressure 600 psi and shut in 0 psi. 9-16-92
3rd plug pumped 115 sx cement down backside. Maximum pressure 800 psi and shut in 300 psi

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. No casing recovery. SEP 16 1992
(If additional description is necessary, use BACK of this form.)

INVOLVED
I, Dan Goodrow, observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

DATE 9-30-92

WV. NO. 36286