

To: 1071097  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-10 API NUMBER 15-083-10248-0000 Drilled 8/62 30

C NW NE, SEC. 21, T. 22 S, R. 22 W/E  
4620 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5363  
Operator: BEREXCO  
Name & Address P.O. Box 723  
Hays, KS 67601

Lease Name Ed Miller Well # 1  
County Hodgeman 146.77  
Well Total Depth 4516 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BEREXCO License Number 5363

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 10:30 a.m. Day: 10 Month: 9 Year: 19 92

Plugging proposal received from Ted Crawford

(company name) BEREXCO (phone) 913-628-6101

work: 5 1/2" at 4514' w/100 sx cement. Perfs at 4414-34, 4437-40, 4177-4208'  
1st plug set CIBP at 4100' and dump 2 sx cement on top,  
2nd plug perforate 5 1/2" at 600', pump 150 sx cement down 5 1/2",  
3rd plug pump 100 sx cement down backside.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 10 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' and dumped 2 sx cement on top,

2nd plug perforated 5 1/2" at 600' and pumped 150 sx cement down 5 1/2". Maximum pressure 1000 psi and shut in 500 psi.

3rd plug pumped 100 sx cement down backside. Maximum pressure 500 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

**INVOLVED**  
I (or I'd) ~~(XXXXXX)~~ observe this plugging.

DATE 9-30-92

Signed Dan Goodrow  
(TECHNICIAN)

WEL. NO. 36287

9-16-92  
RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1992

CONSERVATION DIVISION  
Wichita, Kansas