

To: 1 071013
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-10 15-083-10249-0000
API NUMBER 15- Drill Completion Date 9/28/62

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: BEREXCO INC.
Name & Address P.O. Box 723
Hays, KS 67601

C SW NE, SEC. 21, T. 22 S, R. 22 W/E
3300 feet from S section line
1980 feet from E section line
Lease Name Ed Miller Well # 2
County Hodgeman 158.34
Well Total Depth 4872 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor BEREXCO INC. License Number 5363
Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 11:30 a.m. Day: 10 Month: 12 Year: 19 91

Plugging proposal received from Ted Crawford
(company name) BEREXCO INC. (phone) 913-628-6101

were: 5 1/2" at 4703' w/175 sx cement, 2BTD 4490', Perfs at 4174-4206'
1st plug set CIBP at 4125' with 2 sx cement on top,
2nd plug perforate at 600', pump 80 sx cement,
3rd plug pump 120 sx cement down backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 10 Month: 12 Year: 1991

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' and dumped 2 sx cement on top,
2nd plug perforated at 600', pumped 200 sx cement down 5 1/2". Maximum pressure 350 psi and
shut in 0 psi.
3rd plug pumped 100 sx cement down backside. Maximum pressure 650 psi and shut in 0 psi.

Remarks: Used 65/35 Pozmix 8% gel by B.J. Services. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 1-7-92
INV. NO. 34199

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1991
CONSERVATION DIVISION
WICHITA, KANSAS

Signed Dan Johnson
(TECHNICIAN)