


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County, Sec. 2 Twp. 22 Rge. 12 (E) W (W)
Location as "NE/CNW¹/₂SW¹/₂" or footage from lines N¹/₂ SW SW
Lease Owner Petroleum Inc.
Lease Name Krug Well No. 1
Office Address Derby Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 2-28-48 19
Application for plugging filed 4-19-48 19
Application for plugging approved 4-14-49 19
Plugging commenced 4-3-49 19
Plugging completed 4-11-49 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	250	8 5-8th	250'	
		0	3634	5 1/2	3312	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to ... feet for each plug set.

Dumped 5 sacks cement in bottom of hole, pulled pipe and mudded hole to 250 feet. Dumped 15 sacks cement at 250 feet. Finished mudding hole and put 10 sacks cement in top of surface casing.

4-25-49

RECEIVED
APR 25 1949
STATE CORPORATION COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum Inc.
Address Derby Bldg, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgewick ss.
Charles M. Seale (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles M. Seale
Derby Bldg, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 20th day of April, 1949

My commission expires October 27, 1952
Notary Public.

PLUGGING
FILE SEC 2 T 22 R 12 W
BOOK PAGE 91 LINE 27

LEASE: Krug Well No. 1
 OWNER: Petroleum, Inc., Wichita, Kansas
 LOCATION: N/2 SW SW, Section 2-22S-12W, Stafford County, Kansas
 CONTRACTOR: J. A. Melland, Hutchinson, Kansas
 COMMENCED DRILLING: February 15, 1949 FINISHED DRILLING: February 27, 1949

DRILLER'S LOG OF FORMATIONS:

Surface sand and shale	0	60	
Sand	60	130	
Shale and red bed	130	260	Set & cemented 8-5/8"OD csg. at 250' w/ 150 sacks cement - Finished cementing 6:00 PM, 2-15-49.
Red bed and shale	260	790	
Shale and shells	790	1130	
Salt	1130	1310	
Shale and lime	1310	1475	
Lime	1475	1535	
Lime & sand, hard	1535	1885	
Lime	1885	2160	
Lime and shale	2160	2945	
Lime	2945	3130	
Lime & shale	3130	3280	
Lime	3280	3549	
Chert	3549	3563	
Cherty lime	3563	3580	
Shale and lime	3580	3605	
Lime	3605	3639	5"OD 13.30# Csg. set @ 3634'
Lime	3639	3649	

ROTARY TOTAL DEPTH 3649'

Rotary drilling completed 2/27/49 - Ran drill stem test at 3649', open 45 minutes, recovered 120' of gas cut mud and oil and 230' of oil, no water.

Set and cemented 5"OD casing at 3634' with 50 sacks of cement. Plug pumped down at 5:45 PM, 2/28-49. Casing cemented by Halliburton Process, using Halliburton Bulk cement. Slope tests were taken at 500' intervals and no deflections from vertical were recorded.

I, J. A. Melland, do hereby certify that the above is, to the best of my knowledge and belief, a true and exact record of the Krug Well No. 1.

J. A. Melland

Cable Tool Depth: 3654'
 Production: Dry

JAM

APR - 8 1949

STATE OF KANSAS
 COMMISSIONER
 KANSAS

