


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County, Sec. 2 Twp. 22 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines SE NE NW
Lease Owner Petroleum, Inc.
Lease Name Hitz "A" Well No. 1
Office Address Route 2, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced Jan. 22 19 74
Plugging completed Jan. 29 19 74
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3598 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	225'	8 5/8"	225'	none
			3592'	5 1/2"	3592'	3074.90

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 3290', dumped 20' of sand and 5 sacks of cement.
Plugged well pumping in 2 sacks of hulls, 20 sacks of mud and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 30th day of January, 19 74

My commission expires Feb. 10, 1975
George A. Meyer Notary Public


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
506 East Murdock, Wichita, Kansas

COPY

Company: PETROLEUM, INC.
Farm: Hitz No. 1

SEC. 2 T. 22 R. 12W
SE NE NW

County Stafford
KANSAS



Elevation. 1829

Production. 34 bbls 81% water

Total Depth. 3598
Comm. 10-15-52 Comp. 10-26-52
Shot or Treated.
Contractor Garvey Drilling Co.
Issued. 1-3-53

CASING:
8-5/8 225 w/ 175 sx.
5-1/2 3591 w/ 100 sx.

Figures indicate Bottom of Formations.

sand	130	TOPS	
shale	155		
sand	195	Heebner	3086
shale w shells	225	Brown lime	3217
red shale	615	Lansing	3239
anhydrite	628	Simpson	3537
shale shells	1075	Arbuckle	3590
lime & shale	1765		
lime	2070		
lime w shale	2800		
lime	3085		
lime & shale	3175		
lime	3580		
shale	3590		
lime	3598	T. D.	

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1974

CONSERVATION DIVISION
Wichita, Kansas

DST #1 3292-3315 open 1 hr. rec. 30' oil cut mud, 600' froggy oil, 300' free oil, 810# BHP.

DST #2 3358-3382 open 1 hr. rec. 53' heavily oil cut mud, 478' froggy oil, 2' salt water BHP 1070#

DST #3 3386-3420 open 1 hr. rec. 70' slightly oil cut mud, 100' muddy oil, 10' water BHP 1260#

DST #4 3426-3440 open 40 minutes, rec. 2040' oil BHP 1400#

DST #5 3591-3594 open 1 hr. rec 120' gas, 30' slightly oil & gas cut mud. 0# BHP.