

15-185-21256-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 4 TWP. 23S RGE. 13W E/W
Location as in quarters or footage from lines:

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate Well
correctly on above
Section Platt.

W SE SW
Lease Owner S & L Oil Company
Lease Name Scheib Well No. #1
Office Address P.O. Box 1389 Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 9-15-81
Plugging completed 9-22-81
Reason for abandonment of well or producing formation

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3885'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 338' | none |
| | | | | 5-1/2" | 3883' | 2020' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in on location, plugged off bottom with sand to 3500' and set 5 sacks cement. Took stretch, shot casing @2827', 2740', 2660', 2580', 2502', 2402', 2341', 2260', 2177', 2100' and 2020'. Pulled a total of 50 joints of pipe. Plugged well with 4 sacks hulls, 20 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 2% gel, 3% cc. Plugging Completed.

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

SEP 29 1981

STATE OF Kansas COUNTY OF Rice, ss.

CONSERVATION DIVISION

Wichita, Kansas

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 19 81

My Commission expires: Kelso Casing Pulling

Irene Hoover
Notary Public.

