

15-185-20313-0000


Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

File - All Information Completely  
State Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County, Sec 6 Twp. 23 Rge. 13 (E) W (W)  
Location as "NE/CNW/SW4" or footage from lines NW NE SE  
Lease Owner Wayne J. Kirkman Oil Operations  
Lease Name Corn Well No. #1  
Office Address P. O. Box 143 ; Great Bend, Ks. 67530  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed April 1974  
Application for plugging approved April 1974  
Plugging commenced \_\_\_\_\_ 19\_\_\_\_  
Plugging completed May 3 1974  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	330	None
				5 1/2"	3896	2018

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used  
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Plugged off bottom. Allied Cementing Co. mixed and  
pumped down 5 1/2" casing; 1 sx of hulls, 10 sx of  
gel and 20 sx of cement to 3400'.

May 3, 1974 Plugged off top. Allied Cementing Co. mixed and  
pumped down 8 5/8" surface casing; 2 sx of hulls,  
10 sx of gel and 100 sx of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 17 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor RUSS CASING PULLING, INC.  
Address P. O. Box 1082 ; Great Bend, Ks. 67530


STATE OF Kansas COUNTY OF Sedgwick ss.  
E. F. Day (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. F. Day  
Box 18148, Wichita, Ks 67218  
(Address)

16th. day of July 1974

Maxine Dressen  
Maxine Dressen Notary Public.



K. T. WOODMAN  
Res. PHONE AM 5-3572  
OFFICE PH. AM 5-7650  
WICHITA, KANSAS

D. J. IANNITTI  
TELEPHONE 653-2301  
HOISINGTON, KANSAS

# WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

706 UNION NATIONAL BUILDING

WICHITA, KANSAS 67202

December 22, 1970

15-185-20313-0000

NORTH WELL

Company;	Thornton E. Anderson
Farm:	No. 1 Corn
Location;	E/2
Section;	6-23S-13W
County;	Stafford
Comm;	December 12, 1970
Compl;	December 22, 1970
Total Depth;	3899'
Casing;	8 5/8" @ 330' W/275 sx. 5 1/2" @ 3896' W/125 sx.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Figures Indicate Bottom Of Formations:

100	Sand
290	Sand
330	Blue Shale
550	Shale
835	Red Bed & Shale
1450	Shale, Shells & Salt
1700	Shale & Shells
1810	Lime & Shale
1995	Lime
2210	Lime
2390	Lime & Shale
2710	Shale
2900	Shale
3090	Lime & Shale
3200	Lime & Shale
3255	Lime
3345	Lime
3530	Lime
3609	Lime
3646	Lime
3685	Lime
3745	Lime
3830	Lime
3873	Lime
3884	Lime
3899	Lime

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

*K. T. Woodman*  
K. T. Woodman