

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 6 Twp. 23 Rge. 13 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines ~~SE SE SE~~ NE SE SE

Lease Owner Inger Oil Company

Lease Name KERN Corn Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed _____ 19 _____

Application for plugging approved _____ 19 _____


Plugging commenced 4-9-64 _____ 19 _____

Plugging completed 4-13-64 _____ 19 _____

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3912 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUL IN	PULLED OUT
				8-5/8"	315'	None
				5-1/2"	3910'	3202'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to plug back @ 3659', sanded hole to 3600' and dumped 5 sacks of cement @ 3600' with dump bailer. Pulled 5 1/2" casing, set over-night plug @ 250' with 20' rock bridge to 230', sand to 225' and dumped 5 sacks of cement with dump bailer. Bailed hole to 220' and dumped 20 sacks of cement @ 220'. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1964

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or ~~owner or operator~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of April, 1964

My commission expires May 20, 1964

Milton J. Volin
Notary Public.

15-185-01397-0000

DRILLER'S LOG


COMPANY: Inger Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: CORN #1
 LOCATION: NE SE SE Sec. 6-23S-13W
 STAFFORD COUNTY, KANSAS
 COMMENCED: 3-7-64
 COMPLETED: 3-16-64

0	35	Clay & Sand
35	205	Sand & Gravel
205	245	Shale
245	295	Sand, Dakota
295	794	Redbed
794	828	Anhydrite
828	1300	Shale
1300	1450	Shale & Lime
1450	1615	Shale & Shells
1615	2200	Lime
2200	2395	Lime & Shale
2395	2450	Shale & Shells
2450	2680	Shale & Lime
2680	2960	Lime & Shale
2960	3100	Shale & Lime
3100	3255	Shale & Lime
3255	3361	Lime & Shale
3361	3485	Shale & Sand
3485	3745	Lime
3745	3793	Lime & Conglomerate
3793	3811	Conglomerate
3811	3853	Viola
3853	3857	Simpson Shale
3857	3870	Sandy Lime & Shale
3870	3905	Sand & Shale
3905	3912	Lime
	<u>3912</u>	<u>Rotary Total Depth</u> - Set 5 1/2" Casing

RECEIVED
 STATE CORPORATION COMMISSION
 APR 10 1964
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 326' cemented with 300 sacks Sunset, 2% Gel.


I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Corn #1, located NE SE SE of Section 6, Township 23 South, Range 13 West, Stafford County, Kansas, this 18th day of March, 1964, as reflected by the files of Leben Drilling, Inc.



 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 18th day of March, 1964.



 Ulanda Nichols, Notary Public