

15-185-01270-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County. Sec. 6 Twp. 23 Rge. 13 (E)W. (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NW
Lease Owner J. M. Huber
Lease Name Miller Well No. 1
Office Address Petroleum Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 1-7-48 19__
Application for plugging filed 1-7-48 19__
Application for plugging approved 1-7-48 19__
Plugging commenced 1-7-48 19__
Plugging completed 1-7-48 19__
Reason for abandonment of well or producing formation Low and no shows.

NORTH

0			

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Kerr, Great Bend
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3935 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>8-5/8"</u>				<u>8-5/8"</u>	<u>229.89</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with heavy mud from 3935' to 230'. Drove wood plug down to 226' and filled with 15 sacks cement then mud to 20'. Wood plug set and 10 sacks cement filled into top of hole. Pipe cut off at bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. M. Huber Corp.
Address Petroleum Building, Wichita, Kansas

STATE CORPORATION COMMISSION
JAN 17 1948

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. R. A. Cook, co-owner, (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By R. A. Cook, President
G-G DRIDDLING COMPANY, Inc.
206 Union Natl Bank Bldg., Wichita Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 1948.

My commission expires June 25, 1951

Wicky Fritz
Notary Public.

PLUGGING
FILE SEC 6 T 23 R 13
BOOK PAGE 9 LINE 18

15-185-01220-0000

CONTRACTOR'S WELL LOG

Operator J. W. Huber Corporation Farm Name Miller No. 1
 Location C NW/4 NW/4 Sec. 6, Twp. 23 S, Rge. 15 W.
 Pool Name WT County Stafford State Kansas
 Commencement Date 12-23-47 Completion Date 1-8-48

LOG OF WELL

Elevation 1915'
 *All measurements from the top of rotary bushing.

DEPTH		FORMATION	DIP	
FROM	TO		FROM	VERTICAL
0	230			
230	285	Shale-Red Bed		
285	305	Shale-Red Bed		
305	330	Anhydrite		
330	345	Shale-Shells		
345	1800	Shale-Shells	0°	
1800	1400	Shale-Shells		
1400	1460	Shale-Shells		
1460	1645	Salt-Shale-Shells		
1645	1800	Shale-Shells		
1800	1885	Lime		
1885	1970	Lime	0°	
1970	2080	Lime		
2080	2175	Lime		
2175	2180	Lime		
2180	2240	Shale		
2240	2345	Lime-Shale		
2345	2480	Lime-Shale	0°	
2480	2570	Lime-Shale		
2570	2680	Lime-Shale		
2680	2770	Lime-Shale		
2770	2860	Lime-Shale		
2860	2955	Lime-Shale		
2955	3100	Lime-Shale	0°	
3100	3200	Lime-Shale		
3200	3265	Lime		
3265	3340	Lime		
3340	3405	Lime-Shale		
3405	3475	Lime		
3475	3575	Lime		
3575	3720	Lime		
3720	3845	Lime		
3845	3935	Lime		

RECORDED
 JAN 17 1948

CASING DEPT IS N.E. 1/4 SEC 6 COMPLETION
 229.22' 1-8/8" ID Casing.

STATE OF KANSAS)
 COUNTY OF STAFFORD) ss.

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

C- DRILLING COMPANY, INC.
 By R. A. Cook, Pres.

Subscribed and sworn to before me this 7th day of January, 1948.

My commission expires:
 June 25, 1941

Vicky Fritz
 Notary Public

PLUGGING
 FILE SEC 6-T 23 S 15 W
 BOOK PAGE 9 LINE 18