

15-185-01062-0000

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Stafford County. Sec. 10 Twp. 23S Rge. 13W (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. 330' N & 330' E of SW Cor of SE/4

Lease Owner Magnolia Petroleum Company

Lease Name Morris Garvin Well No. 1

Office Address Box #770, Great Bend, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed May 12, 1947/ 19.

Application for plugging filed May 12, 1947 19.

Application for plugging approved May 12, 1947 19.


Plugging commenced May 12, 1947 19.

Plugging completed May 12, 1947 19.

Reason for abandonment of well or producing formation Drilled dry

If a producing well is abandoned, date of last production..... 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well H. W. Kerr

Producing formation None Depth to top..... Bottom..... Total Depth of Well 3872 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	260'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with heavy mud laden fluid from bottom of hole, 3872' to 250'; Pumped 15 sacks of cement from 250' to 190'; filled with heavy mud laden fluid to 40'; filled top of 8-5/8" surface casing with 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Magnolia Petroleum Company, C. A. Hill, Sup't.
Address Box #770, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

C. A. Hill (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Box #770, Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of May, 1947

My Commission Expires Oct. 3, 1949

My commission expires.....

[Signature]
Notary Public.

PLUGGING
FILE SEC 10 T 23 R 13W
BOOK PAGE 110 LINE 29

MAGNOLIA PETROLEUM COMPANY
 Morris Garvin Well #1
 Center SW SW SE - 10-23S-13W
 Stafford County, Kansas

15-185-01062-0000

Drilling Commenced: 4/24/47
 Drilling Completed: 5/11/47

Casing Record
 8-5/8" Csg. set @ 260' - Cem. w/300 sax-Pulled none

<u>FORMATION:</u>	<u>TOP</u>	<u>BOTTOM</u>
Sand	0	100
Shale	100	135
Red Bed	135	164
Shale & lime	164	260
Red Bed	260	766
Anhydrite	766	786
Shale & shells	786	1400
Shale, shells & salt	1400	1615
Shale	1615	1650
Lime	1650	1680
Sandy lime	1680	1850
Lime	1850	1915
Shale & lime	1915	1990
Lime	1990	1998
Sand	1998	2040
Lime & shale	2040	2160
Shale & lime	2160	2230
Lime	2230	2290
Shale & lime	2290	2405
Lime & shale	2405	2575
Shale & lime	2575	2975
Shale	2975	3010
Lime	3010	3285
Broken lime	3285	3355
Lime & shale	3355	3420
Lime	3420	3469
Broken lime	3469	3520
Lime	3520	3675
Lime & shale	3675	3740
Lime	3740	3765
Chert	3765	3790
Shale & chert	3790	3808
Shale	3808	3852
Lime	3852	3872
Total Depth		3872'.

SAMPLE TOPS:

Lansing-Kansas City	3417	DFM
Conglomerate	3744	"
Viola	3751	"
Simpson	3802	"
Arbuckle	3850	"

DRY AND ABANDONED May 12, 1947.

PLUGGING
 FILE SEC 10 T 23 R 13 W
 BOOK PAGE 110 LINE 29