

15-185-30106-0000


Form GP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 7 Twp. 23S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW NE
Lease Owner Halliburton Oil Producing Company
Lease Name Mason Well No. 1
Office Address 520 Cameron Bldg., Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 18 19 65
Application for plugging filed August 18 19 65
Application for plugging approved August 18 19 65
Plugging commenced August 18 19 65
Plugging completed August 18 19 65
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	332'	8 5/8"	332'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 325'/25 sacks cement/1/2 sack hulls
40'/15 sacks cement/1/2 sack hulls

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1965

CONSERVATION DIVISION
Wichita, Kansas

8-26-65

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 1014 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
D. L. Hellar, Pres. of Hellar Drlg. Co. Inc., (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, Pres.
1014 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of August, 1965

My commission expires March 25, 1968
Catherine Darcey - Notary Public.

15-185-30106-0000

DRILLER'S LOG

COMPANY: Halliburton Oil Producing Company
 CONTRACTOR: Hellar Drilling Company, Inc.
 LEASE: #1 Mason
 LOCATION: NW SW NE 7-23S-13W, Stafford County, Kansas
 COMMENCED: August 11, 1965
 COMPLETED: August 18, 1965
 CASING: Set 8 5/8" surface casing @ 332'/315 sacks cement

0-30	Surface soil & sand
30-200	Sand
200-248	Shale
248-322	Sand
322-332	Shale
332-797	Red Beds & shale
797-819	Anhydrite
819-1400	Red Beds, shale & lime Strks.
1400-1820	Salt Section
1820-1990	Lime & Shale
1990-2100	Cherty Lime & Shale Strks. (Ft. Riley)
2100-2745	Broken Lime & Shale
2745-2943	Shale & Lime Strks.
2943-3236	Lime & Shale Strks.
3236-3341	Shale & Lime
3341-3475	Mostly Shale
3475-3722	Limestone, Broken Shale
3722	Rotary Total Depth
	Dry & Abandoned

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 26 1965
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Mason, located in NW SW NE 7-23S-13W, Stafford County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 24th day of August, 1965.

Catherine Darcey
 Notary Public - Catherine Darcey

My Commission Expires:
 March 25, 1968.