

15-185-00914-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 7 Twp. 23 Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Buick Drilling Inc., et al

Lease Name Thomas Well No. 1

Office Address P. O. Box 331, St. John, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed September 19, 1956

Application for plugging filed September 19, 1956

Application for plugging approved September 19, 1956

Plugging commenced September 19, 1956

Plugging completed September 19, 1956

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3965' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	233'	8 5/8"	233'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy rotary mud from 3965 to 180'. 1/3 sack hulls, one Howco plug and 20 sacks cement, placed through drill pipe. From 180' to 35', 1/3 sack hulls, one Howco plug, and 10 sacks cement.

9-27-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Buick Drilling Inc.

Address P. O. Box 331, St. John, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.

H. R. Buick (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Buick

P. O. Box 331 - St. John, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 56

Robert A. Shogren
Notary Public.

My commission expires December 26, 1959

PLUGGING
FILE SEC. 7 T. 23 R. 13W
BOOK PAGE 101 LINE 22

DRILLERS LOG

15-185-60914-0006

Thomas #1
 Commenced R.D.: 9-2-56
 Completed R.D.: 9-18-56
 Total Depth: 3965'
 Casing Record: 233' of 8 5/8"

SW SW SW Sec. 7-23-13W
 Stafford County, Kansas
 Elevation: 1906' D.F.
 Initial Prod.: None
 Contractor: Buick Drilling Inc.

STRATA	DEPTH
Sand	0 - 124
Sandy shale	124 - 190
Shale	190 - 233
Blue shale	233 - 241
Sand	241 - 338
Red bed and sand	338 - 644
Red bed	644 - 665
Sand and red bed	665 - 705
Red bed	705 - 800
Anhydrite	800 - 842
Sandy shale	842 - 1120
Shale and shells	1120 - 1635
Shale and lime	1635 - 3153
Lime	3153 - 3248
Lime and shale	3248 - 3304
Lime	3304 - 3350
Shale and shells	3350 - 3415
Lime and shale	3415 - 3455
Shale	3455 - 3485
Lime	3485 - 3527
Lime and shale	3527 - 3573
Lime	3573 - 3807
Lime and chert	3807 - 3832
Chert and shale	3832 - 3838
Shale and lime	3838 - 3877
Chert and shale	3877 - 3906
Shale	3906 - 3955
Lime	3955 - 3960
Lime and shale	3960 - 3965 T.D.

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

H. R. Buick
 H. R. Buick, President

Signed and sworn to in my presence this 19th day of September, 1956, by H. R. Buick, President of the Buick Drilling Inc.

Roberta Shoguen
 Notary Public

My commission expires December 26, 1959.

PLUGGING
 FILE SEC. 7 T. 23 R. 13W
 BOOK PAGE 101 LINE 22