

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,708-0000

LEASE NAME Komarek

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 23

2970 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR Hallwood Petroleum, Inc.

SEC. 30 TWP. 22 RGE. 11 (E) or (W)

ADDRESS P.O. Box 378111 Denver, CO 80237

COUNTY Stafford

PHONE# (316) 792-2756 OPERATORS LICENSE NO. 03613

Date Well Completed 09-08-90

Character of Well D&A

Plugging Commenced 09-08-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 09-08-90

The plugging proposal was approved on 09-07-90 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3655

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 3526' w/40 sacks cement thru drill pipe

Next Plug: @ 600' w/50 " " " " " 15 sacks in Rat Hole

Next Plug: @ 280' w/40 " " " " " "

Top Plug: @ 40' w/10 " " " " " water well filled

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hallwood Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~(XXXXXX)~~ of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

SEP 12 1990

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530



9-12-90
SUBSCRIBED AND SWORN TO before me this

11 day of Sept, 1990
Dorothy M. Hague
Notary Public

My Commission Expires: 5-29-94

DRILLER'S WELL LOG

DATE COMMENCED: September 1, 1990
 DATE COMPLETED: September 8, 1990

Hallwood Petroleum, Inc.
 KOMAREK #23
 SW. SE NE
 Sec. 30, T22S, R11W
 Stafford County, Ks.

0 - 120' Surface Soil, Sand
 120 - 550' Red Bed
 550 - 578' Anhydrite
 578 - 1360' Shale
 1360 - 2778' Shale & Lime
 2778 - 3074' Lime
 3074 - 3104' Shale & Lime
 3104 - 3211' Shale
 3211 - 3237' Lime & Shale
 3237 - 3484' Lime
 3484 - 3520' Shale, Lime, Chert, Sand
 3520 - 3541' Sand & Shale
 3541 - 3655' Dolomite
 3655' RTD

ELEVATION: 1826 K.B.

Surface Pipe: Set new
 8-5/8", 23# pipe @267'
 w/125 sacks 60/40 pozmix
 2% gel 3% cc. & 100 sacks
 60/40 pozmix 3% cc.

A F F I D A V I T


STATE OF KANSAS
 COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 11 day of September 1990.

Dorothy M. Hague
 Notary Public



SEP 12 1990