

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 30 Twp. 22S Rge. 11W (X) (W)

Location as "NE/CNW/SW" or footage from lines SE NW SW
Lease Owner Adair Oil Company
Lease Name Nolte Well No. 1
Office Address P. O. Box 7011, Wichita, Kansas 67201
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 11 19 69
Application for plugging filed November 11 19 69
Application for plugging approved November 11 19 69
Plugging commenced November 11 19 69
Plugging completed November 11 19 69
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3665 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------------|---------|------|-----|-------|--------|------------|
| Shale - Red Bed | | 195 | 254 | 8 5/8 | 249 | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 450' dumped 50 sacks through drill pipe, filled hole with mud to 245' dumped 25 sacks cement through drill pipe, filled hole with mud to 40' set plug and dumped 10 sacks cement 1/2 sack hulls. Two Sacks cement in Rat Hole.

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Isern Drilling Company
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. F. Banks, Drlg. Supt. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. F. Banks
Box 486, Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 19 69

My commission expires February 10, 1971.
George A. Meyer
George A. Meyer, Notary Public.

W E L L L O G

Adair Oil Company, NOLTE #1
SE NW SW, Section 30-22S-11W
Stafford County, Kansas

ELEVATION: 1823' GL; 1825' DF; 1827' KB.

Figures indicate bottom of formation:

| | | | | |
|----------------------------|---|----|------|--------------------|
| PIPE RECORD: | 0 | to | 115 | sand |
| 8 5/8" set at 249' | | | 195 | red bed |
| with 250 sacks cement. | | | 254 | shale - red bed |
| | | | 562 | red bed |
| Dry and Abandoned. | | | 1375 | shale |
| | | | 1730 | shale & shells |
| | | | 1765 | shale & lime |
| ROTARY COMMENCED: 11-4-69 | | | 2085 | lime & shale |
| ROTARY COMPLETED: 11-11-69 | | | 2720 | shale & shells |
| | | | 2845 | shale & lime |
| | | | 3130 | lime & shale |
| | | | 3250 | shale & lime |
| | | | 3660 | lime & shale |
| | | | 3665 | Rotary Total Depth |

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1969
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF BARTON) ss

I, W. F. Banks, Drilling Superintendent of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.


W. F. Banks

Subscribed and sworn to before me on this 12th day of November, 1969.


George A. Meyer, Notary Public

My commission expires: February 10, 1971.