


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 30 Twp. 22S Rge. 11W (E) (W)

Location as "NE/CNWSW" or footage from lines SE/4 SW/4 NW/4

Lease Owner Icer Addis

Lease Name NOLTE Well No. 1

Office Address 312 Petroleum Building - Wichita - Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 13 19 73

Application for plugging filed February 13 19 73

Application for plugging approved February 13 19 73

Plugging commenced February 13 19 73

Plugging completed February 13 19 73

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 3684 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud.
Bottom plug set at 245' with 35 sacks cement thru drill pipe
Top plug set at 40' w/1/2 sk. hulls and 10 sacks cement.
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (employee of owner) or (owner/contractor) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson

Box 823-Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of February, 19 73.

Dorothy M. Hague
Notary Public.

My commission expires 4-11-1974

W E L L L O G

DATE COMMENCED: February 4, 1973
 DATE COMPLETED: February 13, 1973

Leor Addis
 NOLE #1
 SE/4 SW/4 NW/4
 Sec. 30, T22S-R11W
 Stafford County, Kansas

ELEVATION: 1835 K.B.

0	-	50'	Clay & Sand Streaks
50	-	135'	Sand
135	-	571'	Red Bed
571	-	592'	Anhydrite
592	-	875'	Red Bed
875	-	1477'	Shale & Shells
1477	-	1555'	Shale & Line Streaks
1555	-	1965'	Line and Shale
1965	-	3123'	Shale and Line
3123	-	3128'	Shale
3128	-	3141'	Line & Shale
3141	-	3156'	Line
3156	-	3262'	Shale
3262	-	3285'	Br. Line
3285	-	3516'	Line
3516	-	3561'	Line & Shale
3561	-	3572'	Conglomerate
3572	-	3618'	Chert
3618	-	3638'	Simp. Shale
3638	-	3646'	Simp. Dolomite
3646	-	3674'	Simp. Shale
3674	-	3684'	Dolomite
		3684'	RED

FORMATION DATA

Anhydrite	571'
Heebner	3123'
Toronto	3141'
Douglas	3156'
Br. Line	3262'
Lansing	3285'
Base K.C.	3516'
Conglomerate	3561'
Viola	3572'
Simpson Shale	3618'
Simpson Dolomite	3638'
Simpson Shale	3646'
Arbuckle	3674'

SURFACE PIPE: Set used
 8-5/8", 28# at 255' with
 225 sacks 60/40 Pozmix,
 2% Gel, 3% Ca.C.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Leonard Williamson of lawful age, does swear and state that
 the facts and statements herein contained are true and correct to the
 best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 14 day of February 1973.

Deborah M. Hagane
 Notary Public

My Comm. Expires:
4-11-1974

RECEIVED
 STATE CORPORATION COMMISSION

FEB 16 1973

CONSERVATION DIVISION
 Wichita, Kansas