


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 30 Twp. 22 Rge. 11 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE-NE-SW
Lease Owner PETROLEUM, Incorporated
Lease Name NOLTE Well No. 1
Office Address 305 East Third Street, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed March 8, 19 52
Application for plugging filed May 22, 19 52
Application for plugging approved May 31, 19 52
Plugging commenced May 31, 19 52
Plugging completed May 31, 19 52
Reason for abandonment of well or producing formation No producible shows.

If a producing well is abandoned, date of last production -- -- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3,690' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 219' | not pulled |
| | | | | 5-1/2" | 3689' | 3,058.65' |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

(Plugged back with plastic to 3,646'.)

Filled hole with sand to 3,635'. Placed 5 sacks cement on top of sand at 3,635'. Mudded up to 215', set rock bridge and ran 15 sacks cement on top of rock bridge. Mudded up to 35', set rock bridge, and filled hole to bottom of cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Rural Route 2
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.
RAUL B. SHIVEL (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Raul B. Shivel*
RFD #2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of June, 19 52

Charlotte Heidman
Notary Public.

My commission expires October 12, 1954

PLUGGING
FILE SEC 30 T 22 R 11 W
BOOK PAGE 18 LINE 25

DRILLER'S LOG NOLTE NO. 1

Petroleum, Inc. & Hogan, Lease Owners Section 30, Twp. 22S, Rge. 11W
 Garvey Drilling Company, Contractor Location: NE NE SW
 Drilling Commenced: February 14, 1952 County: Stafford
 Drilling Completed: February 25, 1952 R.T.D. 3690'
 Casing Record: 8 5/8" @ 219' w/175 sax
 5 1/2" @ 3689'

Figures below indicate bottom of formation:

| | | | |
|-------|----------------------|---|------------|
| 50 | Shale | | |
| 110 | Sand | | |
| 219 | Shale & Shells | | |
| 565 | Red Bed & Shale | 3102 (-1278) | Heebner |
| 585 | Anhydrite | 3243 (-1419) | Brown Lime |
| 1425 | Shale & Shells | 3268 (-1444) | Lansing |
| 1500 | Lime & Shale | 3585 (-1761) | Simpson |
| 1690 | Brown Lime | | |
| 1955 | Shale & Lime | DST #1, 3539-89, open 45 mins., recovered | |
| 2130 | Shale & Shells | 10' mud, -# BHP. | |
| 2305 | Shale, Shells & Lime | DST #2, 3572-3618, open 1 hour, rec. | |
| 2510 | Shale & Shells | 25' mud, 0# BHP. | |
| 2690 | Shale | DST #3, 3614-46, open 45 mins., rec. | |
| 2790 | Shale & Shells | 150' O&GCM, 60' heavily O&GCM, | |
| 3280 | Lime & Shale | 80' muddy oil, 480' oil, 1440#BHP | |
| 3370 | Lime | | |
| 3589 | Lime & Shale | | |
| 3613 | Shale & Sand | | |
| 3618 | Sand | | |
| 3646 | Lime & Shale | | |
| 3690 | Sand & Shale | | |
| 3690' | R.T.D. | | |

I hereby certify that this is a true and correct log of the above mentioned log.

PLUGGING
 FILE SEC 30 T 22 R 10
 BOOK PAGE 11 LINE 25

PETROLEUM, INC.

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

by Charlotte Heidman

Subscribed to and sworn to before me, Da Notary Public, in said County and State, this 29th day of February 1952.

RECEIVED
 STATE OF KANSAS
 JUN 11 1952
 CONSERVATION DIVISION
 Wichita, Kansas

Marjorie Bradshaw

My commission expires: October 27, 1952