

15185-61386-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 4 Twp. 23 Rge. 13 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines: NE SW SWNW  
Lease Owner Jay Kornfeld  
Lease Name Metz Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 11-29-65 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 12-5-65 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3876 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	365'	None
				5-1/2"	3876'	2775'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, pushed plug to 3500', sanded to 3443'  
and dumped 5 sacks of cement @ 3443' with dump bailer.  
Pulled 5 1/2" casing, bailed hole to 200', set rock bridge  
to 190' and dumped 25 sacks of cement @ 190'. Mudded  
hole to 40', set rock bridge to 30' and ran 10 sacks  
of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 15 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1965

My commission expires May 20, 1968  
Milton J. Volin Notary Public.

DRILLER'S LOG

15-185-01386-0000

COMPANY: Inger Oil Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: METZ #1  
 LOCATION: NE SW ~~SW~~ Sec. 4-23-13  
 STAFFORD COUNTY, KANSAS  
 COMMENCED: 10-7-63  
 COMPLETED: 10-17-63

0	280	Sand & Shale
280	790	Shale
790	820	Anhydrite
820	1700	Shale
1700	2410	Lime & Shale
2410	3440	Shale & Lime
3440	3766	Lime
3766	3791	Lime & Chert
3791	3818	Viola
3818	3840	Simpson
3840	3876	Lime & Shale
	<u>3876</u>	<u>Rotary Total Depth</u> - Set 5 1/2" Casing

**RECEIVED**  
 STATE CORPORATION COMMISSION

JAN 21 1966

CONSERVATION DIVISION  
 Topeka, Kansas

Set 8 5/8" 28# used surface casing @ 345' with landing joint cemented with 350 sacks Common with HA5.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Metz #1, located NE SW SW of Section 4, Township 23, Range 13, Stafford County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 18th day of October, 1963.

Ulanda Nichols  
 Ulanda Nichols, Notary Public

My Commission Expires:  
 April 1, 1967

*100 lbs  
 @ cement  
 5 1/2" casing*

Top = 30-65 - Cut 5 1/2" at 3270  
 3066  
 3000  
 Affatted 40 lbs oil  
 Globe Cement 160 lbs  
 Acc 1 - Pipe, did not pull