

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23525-00-00
Spot: N2SWSWNE Sec/Twnshp/Rge: 5-8S-20W
2200 feet from N Section Line, 2310 feet from E Section Line
Lease Name: THYFAULT Well #: 1
County: ROOKS Total Vertical Depth: 3509 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>30742</u>	PROD	5.5	3509		135 SX
Op Name: <u>PALOMINO PETROLEUM, INC.</u>	SURF	8.625	224		185 SX
Address: <u>4924 SE 84TH ST</u>	T1	2.875	3397		
<u>NEWTON, KS 67114</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2017 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GLENN DINKEL Company: PALOMINO PETROLEUM, INC. Phone: (785) 735-8199

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement, 500 # hulls and 14 sx (100 # bags) gel.
Alt II 1468' to surface with 120 sx cement.
Production perforations: 3214' - 3218' LKC, 3421' - 3427 Conglomerate

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2017 12:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3222' and pumped 14 sx gel followed by 50 sx cement w/300 # hulls. Pulled tubing to 1601' and pumped 150 sx cement to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing with 25 sx cement. Visually checked 8 5/8" x 5 1/2" annulus and cement was to surface.

GPS: 39.38811N -099.57431W

Perfs:

Top	Bot	Thru	Comments
3421	3427		
3214	3218		

Remarks: SWIFT SERVICES TICKET # 29986

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

OM

KCC WICHITA

MAR 20 2017

MAR 27 2017

RECEIVED

INVOICED

APR - 7 2017