

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-20362-00-01
Spot: SWSE Sec/Twnshp/Rge: 22-31S-9W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DETMER Well #: 1
County: HARPER Total Vertical Depth: 4423 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>31191</u>	PROD	4.5	4401		<u>150 SX</u>
Op Name: <u>R & B OIL & GAS, INC.</u>	SURF	8.625	246		<u>250 SX</u>
Address: <u>124 N MAIN PO BOX 195</u> <u>ATTICA, KS 67009</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Revd. from: RANDY NEWBERRY Company: _____ Phone: (620) 254-7251

Proposed Plugging Method: As KCC Requires

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/03/2017 4:00 PM KCC Agent: B.J. HOPE

Actual Plugging Report:

Set CIBP @ 3620' capped with 2 sx cement on top. Cut casing pipe off @ 1530' pulled casing. Tripped tubing into 1504' spotted 50 sx class A Cement W/3% CC. Waited 1 hour, tripped tubing to 989' spotted 35 sx cement W/3% CC. Tripped tubing into 305' circulated to surface with 130 sx cement W/3% CC and 100 lbs of hulls.

Perfs:

Top	Bot	Thru	Comments
4406	4416		

Remarks: BASIC ENERGY PROVIDED CEMENT, TICKET #14942

Plugged through: TBG

District: 02

Signed

B.J. Hope

(TECHNICIAN)

Form CP-2/3

INVOICED
APR - 7 2017