

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-22828-00-00  
Spot: SWSSEW Sec/Twnshp/Rge: 5-27S-6E  
344 feet from S Section Line, 3610 feet from E Section Line  
Lease Name: MINARD Well #: 3  
County: BUTLER Total Vertical Depth: 3121 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 9412 E. CENTRAL PO BOX 781775  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3121		125 SX
SURF	8.625	218		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/10/2017 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALAN NATION Company: \_\_\_\_\_ Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/13/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2680, QUALITY WELL SERVICE MIXED & PUMPED 35 SXS CLASS A W/150# HULLS & DISPLACED IN CASING. PERFORATED SQUEEZE HOLES 270'-271'. RIH W/TUBING @ 270', QUALITY ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS TO SURFACE 60/40 POZ MIX. LAYED DOWN TUBING, SWEDGED INTO CASING & PUMPED 105 SXS 60/40 POZ MIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE WITH 20 SXS.

Perfs:

Top	Bot	Thru	Comments
2737	2740		CSG
2714	2720		CSG

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

Form CP-2/3

INVOICED  
APR - 7 2017