

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22474-00-01
Spot: SWNWSE Sec/Twnshp/Rge: 33-26S-6E
1672 feet from S Section Line, 2300 feet from E Section Line
Lease Name: SALTER A Well #: 1
County: BUTLER Total Vertical Depth: 2818 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5120</u>	PROD	4.5	2817		75 SX
Op Name: <u>RANGE OIL COMPANY, INC.</u>	SURF	8.625	215		85 SX
Address: <u>9412 E. CENTRAL PO BOX 781775</u> <u>WICHITA, KS 67278</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALAN NATION Company: _____ Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/09/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 2720', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES 265'-266'. RIH W/TUBING @ 270', QUALITY MIXED & PUMPED 30 SXS 60/40 POZ MIX 4% GEL TO SURFACE. LAYED DOWN TUBING . SWEDGED INTO 4 1/2" CASING & PUMPED 110 SXS 60/40 POZ MIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE W/ 30 SXS. 60/40 POZ MIX 4% GEL.

Perfs:

Top	Bot	Thru	Comments
2776	2783	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

Form CP-2/3

INVOICED

APR - 7 2017