

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-60006-00-01  
Spot: SWSENE Sec/Twnshp/Rge: 30-20S-9W  
4235 feet from S Section Line, 336 feet from E Section Line  
Lease Name: MALONE HAROLD Well #: 1  
County: RICE Total Vertical Depth: 3366 feet

Operator License No.: <u>30458</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>RJM COMPANY</u>	PROD	5.5	3364		120 SX
Address: <u>PO BOX 256</u> <u>CLAFLIN, KS 67525</u>	SURF	8.625	254		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/23/2017 10:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM COMPANY Phone: (620) 786-8744

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/23/2017 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, SHOOT OFF STUCK TUBING @ APPROX. 3037' AND PULL OUT REST OF TUBING. PERFORATE AT 1200', 800', 305'. RUN TUBING BACK INTO TOP OF TUBING FISH @ ABOUT 3030' AND PUMP 50 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING TO 1200'. WAIT 1.25 HR'S AND TAG CEMENT AT 2700'. PUMP 35 SX'S COMMON WITH 3% CC AT 1200' AND PULL TUBING TO 600'. WAIT 1 HOUR AND TAG CEMENT AT 1200'. RUN TUBING BACK TO 800' AND PUMP 35 SX'S COMMON WITH 3% CC WITH CIRCULATION FROM BOTH CASINGS. PULL TUBING TO 305' AND CIRCULATE 60-40 POZ, 4% GEL TO SURFACE FROM BOTH CASINGS. PULL TUBING OUT AND TOP OFF. USED 235 SX'S TOTAL.

Top	Bot	Thru	Comments
3290	3295	CSG	
3278	3280	CSG	

Remarks: GRESSEL OIL FIELD PERF TICKET #1517. COPELAND CEMENT #C-44752. NO CURRENT CP111 ON FILE.

Plugged through: TBG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

Form CP-2/3

INVOICED

APR - 7 2017