

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-21089-00-00  
Spot: SWNE Sec/Twnshp/Rge: 6-16S-34W  
3908 feet from S Section Line, 1982 feet from E Section Line  
Lease Name: EDWARDS TRUST G Well #: 6-1  
County: SCOTT Total Vertical Depth: 4790 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: PO BOX 8050  
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4555		
DVT		2426		CMT TO SURFACE
PROD	5.5	4788	0	WITH 175 SX CMT
SURF	8.625	327		WITH 210 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2017 9:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: TODD A. BROWN Company: RUSSEL OIL Phone: (785) 445-6270

Proposed Plugging Method: PUMP 30 SX CMT WITH 200# HULLS. SPACER TO 2450'. PUMP 250 SX CMT FROM 2500' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/21/2017 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT WITH 200# HULLS FROM 4401' TO 4100'. PUMP 30 BBL SPACER FROM 4100' TO 2800'. PUMP 285 SX CMT FROM 2800' TO 0'. PRESSURE TO 400#. HOLDING. PUMP 5 SX CMT DOWN THE ANNULUS. PRESSURE TO 300#.

Perfs:

Top	Bot	Thru	Comments
4707	4708		
4598	4600		
4397	4401		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.


Plugged through: CSG

INVOICED

APR - 7 2017

District: 01

Signed



(TECHNICIAN)

RECEIVED  
MAR 28 2017  
KCC DODGE CITY

