

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-055-22199-00-00
 Spot: NWNEENE Sec/Twnshp/Rge: 7-21S-33W
4987 feet from S Section Line, 647 feet from E Section Line
 Lease Name: BUERKLE 2133 Well #: 1-7
 County: FINNEY Total Vertical Depth: 5510 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4515		WITH 20 SX CMT
CIBP		5300		
COND	20	120		14 SX
PROD	7	5498	1918	WITH 425 SX CMT
SURF	9.625	1835		WITH 710 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2017 9:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Revd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 03/22/2017 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4515' WITH 20 SX CMT. 3/21/17: LOAD & ATTEMPT TO TEST CASING. WOULD NOT HOLD PRESSURE. RUN CBL. FLUID LEVEL =800'. TOP OF GOOD CMT BEHIND THE 7" WAS 3400'. SCATTERED CMT UP TO 2080'. CUT 7" CASING AT 1918'. SDON. 3/22/17: LAY DOWN 7" CASING. RUN TBG TO 1908' & SPOT 125 SX CMT WITH 2% CC & 200# HULLS. AFTER 1 1/2 HOURS TAG TOC AT 1828'. SPOT ADDITIONAL 40 SX CMT AT 1828'. PULL TO 1200' & LOAD THE HOLE. SPOT 50 SX CMT AT 1200'. FULL CIRCULATION. PUMP 20 SX CMT FROM 64' TO 4'. CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5344	5348		
4691	4698		

INVOICED
 APR - 7 2017

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Ken Jehlik
 SA (TECHNICIAN)

RECEIVED
 MAR 28 2017
 KCC DODGE CITY