

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-055-22135-01-00
 Spot: NENWNWNW Sec/Twnshp/Rge: 36-22S-31W
5118 feet from S Section Line, 4876 feet from E Section Line
 Lease Name: ISAAC FARMS Well #: 1-36H
 County: FINNEY Total Vertical Depth: 4870 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4800		WITH 100 SX CMT
COND	20	120		10 SX 8 SX GROUT
	11 7	5357	2055	WITH 265 SX CMT
PROD	4.5	9271		4947-9271 WITH 450 SX CMT
SURF	9.625	1264		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2017 8:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Recvd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4800'. PLUG AT 2040' WITH 75 SX CMT. PLUG AT 1290' WITH 100 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 90' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 03/17/2017 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4800' WITH 100 SX CMT ON TOP OF PLUG. 1ST PLUG AT 2040' WITH 75 SX CMT. 2ND PLUG AT 1290' WITH 100 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 90' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8472	8779		
8126	8389		
7736	7996		
7346	7609		
6938	7273		
6520	6751		
6203	6440		
5784	6093		
5395	5658		
5005	5268		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C COMMON CEMENT BY ORR ENTERPRISES

Plugged through: TBG

District: 01

RECEIVED
 MAR 28 2017
 KCC DODGE CITY

Signed

Kenn Jeulik
 (TECHNICIAN)

INVOICED

Form CP-2/3

177-7-27