

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-057-20839-01-00
 Spot: SWSESESE Sec/Twnshp/Rge: 34-26S-22W
192 feet from S Section Line, 492 feet from E Section Line
 Lease Name: TASSET 2622 Well #: 1-34H
 County: FORD Total Vertical Depth: 4991 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4900		WITH 100 SX CMT
COND	20	130		WITH 15 YDS CMT
	11 7	5364	1422	WITH 300 SX CMT
	L1 4.5	9743		WITH 500 SX CMT
	SURF 9.625	1225		WITH 405 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2017 10:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4900' WITH 100 SX CMT. PLUG AT 1260' WITH 180 SX CMT. WOC & TAG - 800'. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 03/13/2017 6:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

3/10/17: SET CIBP @ 4900'. CIRCULATED 170 BBL MUD THEN SPOTTED 100 SX CMT ON TOP OF BRIDGE PLUG. 3/13/17: RAN TBG TO 1260' & PUMPED 180 SX CMT. PULLED TBG & WOC 3 HOURS. RAN TBG IN TO 1100' & DID NOT FEEL TOC. DECIDED CMT MAY NOT HAVE SET LONG ENOUGH. PULLED TBG & WOC ANOTHER 2 HOURS. RAN SANDLINE WITH 1 JOINT OF TBG & TAGGED TOC @ 850'. RAN TBG TO 800' & PUMPED AN ADDITIONAL 30 SX CMT. PULLED TBG TO 60' & PUMPED 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8294	8682		
7821	8147		
7286	7750		
6820	7202		
6336	6722		
5840	6224		
5354	5754		


Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL 2% CC BY ORR ENTERPRISES. TMD = 9743'

Plugged through: TBG

District: 01

RECEIVED
 MAR 22 2017
 KCC DODGE CITY

Signed _____



(TECHNICIAN)

INVOICED

APR - 7 2017 om CP-213

Handwritten initials