

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21149-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 33-9S-23W  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: RICE ESTATE Well #: 3  
County: GRAHAM Total Vertical Depth: 4000 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3999		125 SX
SURF	8.625	211		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2017 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JARAMIE Company: SCHECK, TIMOTHY DBA SCHECK Phone: (785) 483-4096

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/700 # hulls.  
Perforations: 3920' - 3923'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/01/2017 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 2700', 2037' and 1260'. Ran tubing to 3624' and pumped 60 sx cement w/250 # hulls. Pulled tubing to 2924' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 2124' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 1125' and pumped 90 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 20 sx cement. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 300 psi.

GPS: 39.22191 -099.89096

Perfs:

Top	Bot	Thru	Comments
3920	3923		

Remarks: QUALITY OILWELL CEMENTING TICKET # 105

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

KCC WICHITA

MAR 07 2017

MAR 27 2017

RECEIVED

Form CP-2/3

INVOICED  
APR - 7 2017