

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-21360-00-01  
Spot: NESEBENE Sec/Twnshp/Rge: 23-16S-27W  
4300 feet from S Section Line, 324 feet from E Section Line  
Lease Name: CLARENCE A OWWO Well #: 2-23  
County: LANE Total Vertical Depth: 4580 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2100		WITH 325 SX CMT
PROD	4.5	4579	0	WITH 140 SX CMT
SURF	8.625	274		WITH 165 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2017 8:30 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Revd. from: MORRIS SMITH Company: TRANS PACIFIC OIL Phone: (316) 252-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 100# HULLS. PULL TBG TO 50' BELOW DV TOOL & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/22/2017 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

RUN TBG TO 4280' & PUMPED 35 SX CMT & 100# HULLS. PULL TBG TO 2101' & PUMPED 160 SX CMT & 400# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 55 SX CMT. TIED ONTO BACKSIDE & PRESSURED UP TO 500#.

Top	Bot	Thru	Comments
4162	4204		

INVOICED  
APR - 7 2017

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMXIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier  
5/A (TECHNICIAN)

RECEIVED  
MAR 28 2017  
KCC DODGE CITY MP