

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-087-20447-00-00
Spot: NENWNW Sec/Twnshp/Rge: 16-10S-20E
5241 feet from S Section Line, 4226 feet from E Section Line
Lease Name: SANDERS Well #: 4
County: JEFFERSON Total Vertical Depth: 1518 feet

Operator License No.: 4624
Op Name: UIHLEIN, TED OIL PROPERTIES
Address: 2407 WHITEHALL MANOR
LAWRENCE, KS 66044

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1533		
SURF	7.625	100		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/10/2017 12:00 PM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: JEFF HAWES Company: GLACIER PETROLEUM CO., INC. Phone: (620) 342-1148

Proposed Plugging Method: PUMP 50' CMT PLUG @ 1400', PUM 50' CMT PLUG @ 700', PUM CMT FROM 150', PLUG TO SURF, FILL VOIDS BETWEEN PLUGS W/GEL.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 01/11/2017 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

RAN 2 3/8" TUBING DOWN TO 1450' AND FILLED THE HOLE WITH GEL. PUMPED A 50' CEMENT PLUG AT 1450'. PULLED THE TUBING UP TO 700' AND PUMPED 50' OF CEMENT. PULLED THE TUBING UP TO 325' AND PUMPED CEMENT TO THE SURFACE.

Perfs:

Top	Bot	Thru	Comments
1473	1479		

RECEIVED
KCC DIST # 3
MAR 23 2017
CHANUTE, KS
TH
INVOICED

Remarks:

Plugged through: TBG

District: 03

Signed Taylor Herman
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
MAR 30 2017
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3