

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20393-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 35-29S-7W
4950 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SULLIVAN Well #: 1
County: KINGMAN Total Vertical Depth: 4195 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4194		125 SX
SURF	8.625	276		225 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/11/2017 12:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Revd. from: TRACY BLACK Company: _____ Phone: (316) 215-1873

Proposed Plugging Method: Per KCC District 2 instructions

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/13/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

set CIBP @ 4075', dumped 2 sx cement on top. 1/12/17: cut casing free @ 1407'. Pull casing up to 1150', spotted 50 sx Class A, 3% cc; let cement set 1 - 1/2 hours. Couldn't find plug, sandline parted, 400' left in hole. Pulled casing. 1/13/17: Tripped tubing into 1100' spotted 50 sx Class A 3% cc and 100# hulls. Tag cement @ 730'. Tripped tubing into 650' spotted 35 sx Class A 3% cc. tag at 570'. Tripped tubing into 350': Circulated to surface 70 sx Class A 3% cc with 200#hulls and 90 sx 60/40 pozmix, 4% gel.

Perfs:

Top	Bot	Thru	Comments
4110	4120		

Remarks: COPELAND OUT OF BURRTON PROVIDE CEMENT. TICKET # 44555, DENIED TA

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

INVOICED
APR - 7 2017

1/4