

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19621-00-02
Spot: SESESENE Sec/Twnshp/Rge: 8-25S-5E
2699 feet from S Section Line, 259 feet from E Section Line
Lease Name: WILSON A Well #: 288
County: BUTLER Total Vertical Depth: 2533 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5030</u>	<u>CIBP</u>		<u>850</u>		
Op Name: <u>VESS OIL CORPORATION</u>	<u>PROD 7</u>		<u>2531</u>		<u>400 SX</u>
Address: <u>1700 WATERFRONT PKWY BLDG 500</u> <u>WICHITA, KS 67206</u>	<u>SURF</u>	<u>10.75</u>	<u>108</u>		<u>70 SX</u>
	<u>TI</u>	<u>2.375</u>	<u>655</u>		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2017 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: _____ Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/20/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 650', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION. MIXED & PUMPED 50 SXS CLASS A COMMON 5% CC W/HULLS & DISPLACED IN CASING. TAGGED CEMENT @ 347'. SQUEEZE HOLES @ 200'-201', SWEDGED INTO CASING, CONSOLIDATED ESTABLISHED CIRCULATION MIXED & PUMPED 95 SXS 60/40 POZ MIX 4% GEL 2% CC TO SURFACE. CEMENT TICKET #52089.

Perfs:

Top	Bot	Thru	Comments
668	680	CSG	

INVOICED
APR - 7 2017

Remarks: DENIED TA. / BOND LOG SHOWED CEMENT TOP @ 225'.

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)