

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23499-00-01
Spot: NESESENW Sec/Twnshp/Rge: 8-25S-5E
3165 feet from S Section Line, 2875 feet from E Section Line
Lease Name: WILSON A Well #: 422
County: BUTLER Total Vertical Depth: 1485 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1000		
CIBP		1470		
PROD	5.5	1482		270 SX
SURF	8.625	264		135 SX
T1	2.375	930		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: _____ Phone: (316) 655-1997

Proposed Plugging Method: Per KCC District 2 instructions

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/24/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 900', CONSOLIDATED OIL WELL SERVICES PUMPED 1400# SAND. 3-4-2017, RIH W/TUBING @ 790'. CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 87 SXS 60/40 POZ MIX 4% GEL 50# HULLS TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/3 SXS. SIP 300#. TICKET #51988.

Perfs:

Top	Bot	Thru	Comments
1434	1448	CSG	
1402	1418	CSG	
1386	1396	CSG	
940	948	CSG	
930	932	CSG	
678	690	CSG	
578	583	CSG	

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

INVOICED
APR - 7 2017