

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21794-00-00
Spot: S2SEWNNE Sec/Twnshp/Rge: 14-26S-4E
1000 feet from N Section Line, 1650 feet from E Section Line
Lease Name: HAMILTON A Well #: 30
County: BUTLER Total Vertical Depth: 2421 feet

Operator License No.: <u>5030</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>VESS OIL CORPORATION</u>	PROD	4.5	2400		250 SX
Address: <u>1700 WATERFRONT PKWY BLDG 500</u> <u>WICHITA, KS 67206</u>	SURF	8.625	210		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2017 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Revd. from: CASEY COATS Company: _____ Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 03/24/2017 11:35 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2400', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS CLASS A COMMON 50# HULLS & DISPLACED IN CASING. TAGGED CEMENT @ 1557. RIH W/TUBING @ 250'. CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS 60/40 POZ MIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/10 SXS. TICKET #52093.

Perfs:

Top	Bot	Thru	Comments
2400	2421	OH	

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

INVOICED
APR - 7 2017

14