

To: 1 120518  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30385

Operator: Liedtke Partners  
Name & Address P.O. Box 1605  
Great Bend, KS 67530

1-11 15485-01985.0000 49  
API NUMBER 15-Drill Completion Date 8/24/42  
C. NW SE, SEC. 7, T. 22 S, R. 12 WE  
1980 feet from S section line  
1980 feet from E section line

Lease Name Alpers Well # 5  
County Stafford 119.92  
Well Total Depth 3690 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 231

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 4:30 p.m. Day: 11 Month: 1 Year: 19 91

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 7" at 3688' w/150 sx cement, PBTB 3565', Perfs at 3495-3504'  
1st plug sand 7" casing back to 3445' and dump 6 sx cement on top of sand through bailer,  
2nd plug perforate 7" casing at the base of the Anhydrite and run tubing below the  
perfs, circulate cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:30 p.m. Day: 11 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 7" casing back to 3398' and dumped 6 sx cement  
on top of sand through bailer,  
2nd plug pressured 7" casing to 200#, pressure dropped to 50# in 15 minutes, perforated  
7" casing at 726', ran tubing to 750', and circulated cement in 7" casing and the  
backside with 300 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE FEB 12 1991  
INV. NO. 30695

Signed Duane Rankin  
(TECHNICIAN)