

To: 1 052185 10-29  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Drilled 9/22/48

SE SE SW, SEC. 7, T 22 S, R 12 WXX

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 6170

Lease Name Alpers Well 7 11-4-97

Operator: Globe Operating, Inc.

County Stafford 19.47

Name & Address

Well Total Depth 3676 feet

P.O. Box 12

Conductor Pipe: Size feet

Great Bend, KS 67530

Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1 p.m. Day: 29 Month: 10 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-792-7607

Work: 5 1/2" at 3674' w/150 sx cement, Open hole 3674-76'

1st plug sand back to 3625' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3 p.m. Day: 29 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3625' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1700' of 5 1/2" casing.

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 11-4-97

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 49436