

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-11165-00-00  
Spot: NWNE Sec/Twnshp/Rge: 7-22S-12W  
660 feet from N Section Line, 510 feet from W Section Line  
Lease/Unit Name: CORA B CRAWFORD Well Number: 2  
County: STAFFORD Total Vertical Depth: 3670 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

Production Casing Size: 5.5 feet: 3666 WITH 125 SX CMT  
Surface Casing Size: 9 feet: 289 WITH 200 SX CMT

\$119.<sup>28</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/21/2003 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: BUD BRUNGARDT Company: ALLIED CEMENT COMPANY Phone: (620) 793-5861

Proposed Plugging Method: PUMP 50 SX CMT & 300# HULLS. CMT TO SURFACE. PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/21/2003 11:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:


OPEN HOLE 3666-3670'. SUBMERSIBLE PUMP & TUBING STUCK IN HOLE. TOP OF TUBING FISH @ 2200'. PUMPED DOWN 5 1/2" WITH 50 SX CMT FOLLOWED BY 35 SX CMT WITH 50# HULLS MIXED IN. 1000' OF CMT. PRESSURED TO 2100 PSIG. SHUT IN WITH 2100 PSIG. PUMPED DOWN 9" X 5 1/2" ANNULUS WITH 260 SX CMT WITH 50# HULLS MIXED IN. MAXIMUM PRESSURE 400 PSIG. SHUT IN PRESSURE 250 PSIG.

RECEIVED  
MAY 27 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 5-29-03  
FILE NO. 200306.1576