

1 120424

5-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,370-0000

NW SW SE, SEC. 16, T 22 S, R 12 W/X

990 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588
5111

Lease Name Spangenberg Well # 119.93

Operator: Woodman-Iannitti Oil Company

County Stafford

Name & Address P.O. Box 308

Well Total Depth 3690 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet 5-30-90

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 24 Month: 5 Year: 19 90

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3686' w/100 sx cement, Open hole prod. 4'

1st plug sand back to 3640' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Mike Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 24 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3635' and dumped 5 sx cement on top of
sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2482' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if oil or gas) observe this plugging.

DATE 6-6-90

Signed [Signature]
(TECHNICIAN)

WELL NO. 28352