

1 120442

6-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
40 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,809-0000

SW NW SE, SEC. 16, T 22 S, R 12 W/X
1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name Spangenberg Well # 1

Operator: Woodman Iannitti Oil Company
Name & Address P.O. Box 308

County Stafford 120.12

Great Bend, KS 67530

Well Total Depth 3696 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well X Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 29 Month: 6 Year: 19 90

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3691' cemented w/125 sx, Open hole

1st plug sand back to 3640' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12 p.m. Day: 29 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3640' and dumped 5 sx cement

on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Pumping pressure 0-500 psi and shut in 300 psi.

JUL - 6 1990

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2546' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 7-10-90

INV. NO. 28576