

1 080546

145-R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,280-0000
NE SE NE, SEC. 16, T. 22 S, R. 12 W/E
3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6566

Lease Name Willinger T Well # 1

Operator: Leben Oil Corporation

County Stafford 119.34

Name & Address P.O. Box 21468

Well Total Depth 3672 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kaiser-Francis Oil Company License Number 6568

Address P.O. Box 35528 Tulsa, OK 74135

Company to plug at: Hour: 9:15 a.m. Day: 22 Month: 8 Year: 19 86

Plugging proposal received from John Glenn

(company name) Kaiser-Francis Oil Comp. (phone) 918-494-0000

were: 5 1/2 at 3672' No PBTD Perfs at 3308' Anhydrite 668'

1st plug sand back to 3230' and dump 5 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls, 15 sx jel, 50 sx cement, 10 sx jel, 1 sx hulls, 120 sx cement.

120 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 22 Month: 8 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3230' and dumped 5 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls, 15 sx jel, 50 sx cement, 10 sx jel, 1 sx hulls, and 120 sx cement.

Maximum pressure 450 psi and shut in 400 psi.

Remarks: Recovered 1520' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 28 1986

DIV. NO. 14829

8-27-86 signed _____

J. R. [Signature]
(TECHNICIAN)

AUG 27

8-22