

To: 1 052089  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 185-22,797-0000  
35' E of NW SE NE, SEC. 16, T 22 S, R 12 WXX

TECHNICIAN'S PLUGGING REPORT

Operator License / 5614  
Operator: Hutchinson Oil Company  
Name:  
Address P.O. Box 521  
Derby, KS 67037

3630 feet from S section line  
995 feet from E section line  
Lease Name Willinger Well # 1-16  
County Stafford 122.36  
Well Total Depth 3765 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 672

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1 p.m. Day: 5 Month: 12 Year: 19 96

Plugging proposal received from Kent Strube  
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at 3764' w/125 sx cement, PBSD 3640', Perfs at 3430-3713'  
1st plug sand back to 50' above perfs and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Bill Johnson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 2 p.m. Day: 5 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3380' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released  
8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1835' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE DEC 12 1996  
INV. NO. 47163

Signed Richard M. Lacey  
(TECHNICIAN)