

To: 1 120531
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

Operator: Hallwood Petroleum, Inc.

Name & Address P.O. Box 378111

Denver, CO 80237

2-13 15.185.20224-0000 148
API NUMBER 15- Drilled 12/69
SE NE NE, SEC. 16, T 22 S, R 12 W/E

4290 feet from S section line

330 feet from E section line

Lease Name Willinger Well # 1

County Stafford 119.04

Well Total Depth 3663 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 13 Month: 2 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3410' w/125 sx cement, PBD 3410', Perfs at 3348-51'

1st plug sand back to 3300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

STATE OF KANSAS 2-18-91

FEB 18 1991 Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 13 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3300' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2534' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (void / ~~expired~~) observe this plugging.

DATE 2-26-91

INV. NO. 30901

2-13

Signed Duane Rankin
(TECHNICIAN)