

11-8

To: 1 120161
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,874-0000
NE SE SW, SEC. 16, T 22 S, R 12 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5057

990 feet from S section line
2970 feet from E section line
Lease Name Teichmann-Horyna Unit
Well # 1

Operator: Voight Oil & Gas Company, Inc.
Name & Address RR 3, Box 33-B
McPherson, KS 67460

County Stafford 120.32
Well Total Depth 3702 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 8 Month: 11 Year: 19 88

Plugging proposal received from Clay Duntz
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3683' Open Hole
1st plug sand back to 3630' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1988
CONSERVATION DIVISION
Wichita, Kansas

11-15-88

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed Hour: 3 p.m. Day: 8 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3630' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-750 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2553' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-21-88
INV. NO. 23055

Signed Duane Rankin (TECHNICIAN)