

11-8

1 120162

API NUMBER 15- 185-21,830-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION E/2 NE SW , SEC. 16 , T 22 S, R 12 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1980 feet from S section line

2970 feet from E section line

Teichmann-Horyna Unit  
Lease Name Well # 1-16

TECHNICIAN'S PLUGGING REPORT

Operator License # 5057

County Stafford 123.37

Operator: Voight Oil & Gas Company, Inc.

Name & Address RR 3, Box 33-B

Well Total Depth 3796 feet

McPherson, KS 67460

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 8 Month: 11 Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3794' PBSD 3680' Perfs at 3308-3560' (8 sets)

1st plug sand back to 3260' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 500 lbs. hulls, 20 sx gel and 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1988  
11-15-88

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:45 p.m. Day: 8 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3260' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-800 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2564' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 11-21-88

INV. NO. 23056