

To: 1 120443
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-29 15-185-21922-0000
API NUMBER 15- Docket #D-23,306
E/2 NW SE, SEC. 16, T. 22 S, R. 12 W/E
1980 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6588
Operator: Woodman-Iannitti Oil Company
Name & Address: P.O. Box 308
Great Bend, KS 67530

Lease Name Spangenberg Well # 2
County Stafford 127.63
Well Total Depth 3927 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 29 Month: 6 Year: 19 90

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" casing set at 3840' cemented w/150 sx, Perfs at 3370-72'

1st plug sand back to 3320' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 29 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3320' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-500 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix .6% gel by B.J. Services. Recovered 2539' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
7-6-90
JUL 6 1990

INVOICED
observe this plugging.

Signed *Dennis Rankin*
(TECHNICIAN)

DATE 7-10-90
INV. NO. 28577