

1 080450

*R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,077-0000  
(Spot location corrected by Don C. Ubel)  
C SW NW, SEC. 2, T23 S, R 13 *(W/X)*

3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Mawhirter Well # 2

Operator: Vac Petroleum Co.

County Stafford *124.25*

Name & Address 333 North Rock Road, Suite 105

Well Total Depth 3823 feet

Wichita, KS 67206

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 pm Day: 26 Month: November Year: 19 85

Plugging proposal received from Norman Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3821' PRTD 3810' Perfs at 3481-84'; 3578-84'; 3598-3604'; 3780-82';  
~~3792-94'~~

1st plug sand back to 3430' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 pm Day: 26 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3430' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 200 psi and shut in 50 psi

Remarks: Recovered 2172' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE DEC 10 1985

Signed *J. A. Metz* (TECHNICIAN)

INV. NO. 11386

DEC 5 1985  
12-5-85  
CONSERVATION DIVISION  
Wichita, Kansas