

To: 1 041155  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202  
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- Docket #D-23,758 15-185-21076-0000  
W/2 SW NW, SEC. 2, T 23 S, R 13 W/E  
3300 feet from S section line  
4950 feet from E section line

3-6

Operator License # 5893  
Operator: Pratt Well Service Inc.  
Name & Address: P.O. Box 847  
Pratt, KS 67124-0847

Lease Name Mawhirter Well # 3 SWD  
County Stafford 127.72  
Well Total Depth 3930 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service Inc. License Number 5893  
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 3 Year: 19 96

Plugging proposal received from Fred Mease  
(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 5 1/2" at 3900' w/175 sx cement, Open hole 3900-30'  
1st plug sand back to 3237' and dump 5 sx cement on top of sand through bailer,

2nd plug dump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

3-8-96

KANSAS SECTION  
REGISTRATION  
NO. 119-3-12-96

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 6 Month: 3 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 3237' and dumped 5 sx cement on top of sand  
bridge through bailer,

2nd plug dumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1530' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby observe this plugging.

MAR 13 1996

DATE  
INV. NO. 45040

Signed Stephen J. Feigler  
(TECHNICIAN)